سمبلكس المؤيد
SIMPLEX ALMOAYYED

To,
M/s. Cinqo Contracting W.L.L Flat 141, Building 155, Block 317, Road 1703 Diplomatic Area, Kingdom of Bahrain Tel: 77225050 / 77226060 E-mail: eng3@cinqo-me.com

Quote Details	
Quote Ref:	**Draft**
Quote Date:	29-Oct-2026
Validity:	13-Nov-2026 (15 days)

Customer Ref:	SXPP0279
Type:	Re-Tender
Prepared By:	Merin Kurian
Contact:	+973 33610281
E-mail:	Simplex.Office@almoayyedcg.com

Project Name:	Proposed Seef Mall Repositioning - Pavilion & South Car Park
Subject:	Revised Offer for Piling works (Value Engineering Proposal)
Attention of:	Mr. Siby Joseph

Dear Sir/Madam,

Thank you for providing us with this opportunity to submit our offer for the below-mentioned inclusions. We have carefully reviewed your requirements to ensure that our proposal aligns perfectly. We are pleased to submit our quotation as per the details mentioned below. It is our pleasure to serve you and we assure you that our best efforts will always be made to meet your needs.

We hope you will find our offer competitive and kindly revert to us for any clarifications.

For Simplex Almoayyed W.L.L,

Udayababu D Achary
General Manager

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

1. Basis of the Offer

With reference to the discussions and addition of static pile tests, we are pleased to submit our revised offer (Value Engineering Proposal) for the piling works.

If the Main Contractor supply the concrete (45 N/mm^2) and steel, the corresponding amounts shall be deducted as per the actual consumption at site from Simplex's progressive billing at the rate of BD 31.500/m^3(Without ICE) for concrete and BD 345.000/ton for steel.

The approximate quantity considered for Concrete is 1125 m3 and for steel (fabricated pile cages) is 66 ton, including test piles.

Any additional tests required by the client/consultant requirement, other than mentioned in our BOQ shall be charged additionally, on pro rate basis.

In the event of any discrepancy between the soil investigation report and the actual soil conditions encountered during drilling, the pile lengths shall be re-evaluated and revised accordingly. Any increase in pile length arising from such discrepancies shall be charged on a pro-rate basis.

Since the boreholes were terminated at a depth of 13.0 m, we have assumed that the same soil parameters will continue beyond this depth and have adopted these values for the design up to the required pile depth.

As this is our Value Engineering Proposal, any variations arising during the final design or due to Consultant comments, which are not included in our BOQ, shall be charged on a pro-rate basis.

The quantities and pile layout have been prepared based on the architectural drawings provided and the discussions held, and shall be approved by the Consultant prior to execution.

The supply, installation, shifting, removal, and installation of the MS plates shall be under the scope and responsibility of the Main Contractor. The underground services that are required to be re-routed at the site shall be protected using 25 mm thick MS plates, covering a maximum length of 40 running meters at any one time. Upon completion of the works in the respective area, the MS plates shall be removed and relocated to the subsequent work area as required, allowing the same plates to be reused progressively along the required route. Proper access for our heavy machinery to reach the required site locations, including any demolition works required for access, shall be arranged by the Main Contractor. The site shall be properly levelled and uniformly compacted prior to the mobilization of our machinery. Removal of any underground structures, re-routing of underground services, and relocation or protection of overhead services, providing light arrangement for late night work shall be under the scope of the Main Contractor. Obtainingall necessary permissions for carrying out work during late-night hours shall be the responsibility of the Main Contractor. During pile execution works, vibrations may occur as a result of the piling operations. The Main Contractor shall take the necessary measures to prevent any significant damage to existing structures within or in the immediate vicinity of the site. For tender clarifications please contact Mr. Mohammed (33523334).

2. Scope of Work

2. 01 Bored Cast in situ Piles Piles with diameters as mentioned here in the BOQ.

Pile length and top of steel reinforcement are considered from the EGL(0.00)/ piling platform level.

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

3. Pricing & Payment Terms

Description	Amount (BHD)
Simplex Project	BHD 88,000.000
Total	BHD 88,000.000
VAT 10%	BHD 8,800.000
Grand Total with VAT 10%	BHD 96,800.000

3.1. Our [Lump sum price / total quotation amount] for the scope mentioned above shall be BHD 96,800.000 (Bahraini Dinars Ninety Six Thousand Eight Hundred only.).

3.2. A detailed Bill of Quantity is provided in Annexure B, detailing the Itemized Pricing.

3.3. Payment Terms:

3.3.1. Advance Payment: [Percentage] % upon signing the agreement

3.3.2. Progress Payments: [Percentage] % as per completion milestones

3.3.3. Final Payment: [Percentage] % upon project completion and acceptance

Additional payment milestone for pagination regression.

Second payment milestone for pagination regression.

4. Assumptions- General, Ground Conditions,Concrete ,Steel

3.01 General

The quantities are based on the column reactions & comments provided by the Post Tension & Pile Cap Designer on 11-10-2026 and soil investigation report ,if any extra quantities arising during the final design or site execution stage, which will be charged on pro rate basis.

Eccentric piles are designed in such a way that the moment arising due to the eccentricity is partially (50%) govern by the pile cap and tie beam and partially (50%) by the pile. No reduction in group efficiency considered assuming enough spacing can be provided between piles.

We have designed the pile lengths based on our review of the available soil investigation reports. If any discrepancy is observed between the actual soil conditions encountered at site and the soil borehole logs, the pile lengths shall be rechecked and reviewed before proceeding with further piling works.

The pile is designed as a column and the minimum percentage of reinforcement considered is 0.4% (BS 8110-1-1997, table 3.25)

Lateral load considered is 5% of the safe working load.

If any type of extra pile test carried out as per consultant's requirement, which is not mentioned in our BOQ, additional will be charged as per the actuals.

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

		Any other type of insurance required as per the project specific other than mentioned in our BOQ shall be charged additionally as per the actuals. We have considered installation of temporary casing by Vibro hammer or rotary as per site requirement.
3.02	Ground conditions	We have not considered costs for any cavities, caverns or voids in the ground; Simplex Almoayyed shall not be responsible for any damages on piles due to voids in ground.
3.03	Concrete	Strength of concrete is 45N/mm^2 (for cubes).
3.04	Steel	Non epoxy coated steel Fy460 MPA- Saudi steel/Manama steel

5. Our references

4.01	Drawings	AR-CP-201/BH24-C003,Rev 01 dated Aug 2026 & UG Tank reactions as received on 30.09.2026
4.02	Geotechnical Report	G25-7883;M/s. Al Hoty
4.03	Engineering Standards	BS 8004- BS 8110
4.04	Pile Load Test	Federation of Piling Specialists-February 2006

6. General Conditions

5.01	the corresponding amounts shall be deducted as per the actual consumption at site from Simplex's progressive billing at the rate of BD 31.500/m^3 for concrete and BD 345.000/ton for steel.
5.02	Idle charges, if any due to no reasons of SIMPLEX ALMOAYYED @ BD 100/Hour/rig.
5.03	Necessary security shall be provided for our machineries during non-working hours.
5.04	In case to penetrate through rock of high compressive strength beyond normal mudstone/siltstone, additional charge of BD15-20 to be paid per running meter for such drilling.
5.05	The prices quoted by SIMPLEX ALMOAYYED are based on the prevailing market conditions, taxes, duties, levies, subsidies and utility charges. Notwithstanding anything contained in the other provisions of the agreement, the Parties agree that the Contract Price shall be adjusted to account for any increase in Cost of labor, materials or any other matters affecting the cost of the execution of the Works.
5.06	The Price quoted by us excludes Value Added Tax (VAT) imposed by the concerned authority in Kingdom of Bahrain which shall be payable additionally by the Client/End user.
5.07	Normal Working Time – 6am to 6pm from Saturday to Thursday except public holidays. It may vary during summer restriction time.
5.08	Simplex Almoayyed is not responsible for any kind of damage to the neighbouring buildings due to Pile execution works.
5.09	If the Main Contractor/ client excavate the plot within 14 days from the completion date of piling works, Simplex Almoayyed will not take any responsibility for the pile damages occurred during pile trimming or excavation works.
5.10	The proposed pile length is as per simplex design, if the consultant/Client have any objection or comments on the length during execution time, the additional shall be charged on pro rate basis.

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

7. Validity of offer

6.01 1 month from date of offer

8. Payment Conditions

7.01 a) 25% of contract value as advance payment as current dated cheque upon signing the contract agreement

b) Balance of contract value shall be paid against monthly progressive billing. The Main Contractor shall release the payment within 07 days from the date of submission of invoice.

c) If the Main contractor supply the concrete(45 N/mm2) and the steel, the corresponding amounts shall be deducted as per the actual consumption at site from Simplex progressive bills at the rate of BD 31.50/m3 for concrete and BD 345/ton for steel.

7.02 No retention of money is accepted

7.03 No provision for submission of guarantee cheque against the advance payment

7.04 No provision for submission of the performance bond

9. Programme of work

8. 01 It can be discussed and agree upon requirements of main construction programme.

10. Mobilization

9.01 Mobilization can be done only after getting the clearance for the utilities crossing the plot from the Damage Prevention control Unit (DPCU)-EWA through the main contractor.

9.02 Notice Period : 1 week after issuing LOI

11. Quality Assurance

10.01 Simplex Almoayyed is proud of its high level Quality Control system which enables our site and project management to record and report daily productions, non-conformance reports (NCR), supplier deliveries etc.... These provide the opportunity both for the client and our management to follow,review the flow of the foundation works on site and intervene or amend processes should that be required.

12. Occupational health and safety

11.01 Prior to commencing of any works on site, a site specific Safety Management Plan including Job Safety Analysis(JSA),Plant Hazard Assessment(PHA) and Safe Working Method Stateents (SWMS) will be prepared and submitted to the Client for review.

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

13. Notes

Sl No	Description							Unit	Qty (Nos)	Rate (BD)	Amount (BD)
1	**Mobilization and Demobilization**							Item	1	L.S	2,500.000
2	**Setting out pile positions**							Nos	141	L.S	1500.000
3	**Design and installation of insitu concrete piles**										
							Steel %				
	3.10	P1	-	600 mm dia -	900	kN - 10.00 m	0.4	Nos	4	390.000	1,560.000
	3.20	P2	-	700 mm dia -	2100	kN - 11.50 m	0.4	Nos	6	517.500	3,105.000
	3.30	P3	-	800 mm dia-	3000	kN - 11.50 m	0.7	Nos	4	621.000	2,484.000
	3.40	P4	-	900 mm dia-	3600	kN - 11.50 m	0.6	Nos	18	713.000	12,834.000
	3.50	P5	-	900 mm dia-	4000	kN - 12.00 m	0.9	Nos	7	780.000	5,460.000
	3.60	P6	-	700 mm dia -	2400	kN - 12.00 m	0.4	Nos	11	540.000	5,940.000
	3.70	P7	-	600 mm dia -	2000	kN - 12.00 m	0.7	Nos	10	504.000	5,040.000
	3.80	P8	-	700 mm dia-	2750	kN - 12.50 m	0.5	Nos	13	575.000	7,475.000
	3.90	P9	-	800 mm dia -	3200	kN - 12.00 m	0.4	Nos	9	612.000	5,508.000
	3.10	P10	-	800 mm dia -	3600	kN - 13.00 m	0.4	Nos	10	663.000	6,630.000
	3.11	P11	-	800 mm dia -	4100	kN - 14.00 m	0.7	Nos	14	756.000	10,584.000
	3.12	P12	-	900 mm dia -	4500	kN - 13.50 m	0.4	Nos	5	810.000	4,050.000

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

Sl No	Description	Unit	Qty (Nos)	Rate (BD)	Amount (BD)
	3.13 P13 - 900 mm dia - 5000 kN - 15.00 m 0.4	Nos	4	900.000	3,600.000
	3.14 P14 - 900 mm dia - 4300 kN - 13.00 m 1.4	Nos	2	910.000	1,820.000
	3.15 P15 800 mm dia - 3500 kN - 12.50 m 0.4	Nos	12	637.500	7,650.000
	3.16 P16 700 mm dia - 2600 kN - 12.50 m 0.4	Nos	12	562.500	6,750.000
	Total No of piles		**141**		
4	**Pile Testing**				
	4.1 Non-Working compression load test (2.5 x SWL) on pile type P10-800 mm diameter pile by Static method	No	1	4,500.00	4,500.000
	4.2 Working compression load test (1.5 x SWL) on pile type P13-900 mm diameter pile by Static method.	No	1	3,350.00	3,350.00
	4.3 Working compression load test (1.5 x SWL) on pile type P16-700 mm diameter pile by Static method.	No	1	2,300.00	2,300.00
	4.4 Non-Working compression load test (2.5 x SWL) on pile type P10-800 mm diameter pile by Dynamicmethod	No	1	1,500.00	Rate Only
	4.5 Working compression load test (1.5 x SWL) on pile type P13-900 mm diameter pile by Dynamic method.	No	1	1,000.00	Rate Only
	4.6 Low Strain Integrity test on all piles	Nos	141	L.S	1,010.00
5	**Spoil removal from pile bores and keeping it aside of the plot**	Item	1	L.S	2,000.00
6	**Pile trimming works**	Item	1		By Main Contractor
7	**Professional Indemnity Insurance policy with a 10-year Extended Reporting Period**	Item	1	1,850.000	1,850.000
	Total Amount – Bahrain Dinars –One Hundred Nine Thousand FiveHundredOnly				**109,500.000**

·The Main Contractor shall supply Concrete (45 N/mm²) at BD 31.500/m³ and Steel at BD 345.000 per Ton. The net value of the concrete and steel supplied by the Main Contractor shall be deducted from Simplex progressive bills

• The quoted price for the dynamic test covers the general test report only. Any detailed interpretation, analysis, or correlation with other test results/design parameters, if required, shall be chargedadditional.

Note:

14. Responsibility Matrix

Sl.	Description	Main Contractor	Simplex Almoayyed	Remarks
	General			
1	Soilinvestigation	☑		
2	Design Proposal		☑	

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

Sl.	Description	Main Contractor	Simplex Almoayyed	Remarks
3	Verification and Approval of design	☑		**By Consultant**
4	Redesign of pile cap	☑		
5	Any type of survey work		☑	
6	Removal of excavated material from the pile bore holes and keeping it aside of the site		☑	
7	Firm and level access to all piles locations	☑		
8	Storagesoffice,adequate site officeto piling contractor	☑		
9	Over timeifrequired to consultant	☑		
10	Third Party Insurance for any liability, due to Simplex Almoayyed machines		☑	
11	Any other type of insurance required as per the project specific.	☑		
12	Permits and licenses from the Govt. Authorities	☑		
13	Any removalor relocation ofunderground services and or obstructions or relocation of cables and overhead lines	☑		
14	Penalties for unidentified service damage	☑		
15	NOC from neighboring buildings	☑		
16	Necessary security for our machineries and tools	☑		
17	Electricity and Water	☑		
18	Necessary lighting for executing work at night & Obtaining permission	☑		
19	Required amenities such as toilet, wash area, rest area for site staff	☑		
20	Accommodation and Transportation		☑	
21	Method statement		☑	
22	Mobilization & Demobilization		☑	
23	Boring up to required depth		☑	
24	Steel cage supply with binding wire and spacers		☑	
25	Concretesupplywith pump if necessary		☑	
26	Steel cage installation and concreting		☑	
27	Testing of piles as per Simplex BOQ		☑	
28	Plastic sleeves for the reinforcement above cut off level	☑		
29	Trial Pit as per the EWA requirement	☑		

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com

Sl.	Description	Main Contractor	Simplex Almoayyed	Remarks
30	Any test on concrete other than compressive strength of concrete cubes	☑		
31	Arranging access to reach site location for machines	☑		
Provided by ☑				

Simplex Almoayyed W.L.L
CR No.: 58313-1 PO Box 32617, Building No. 550, Road No. 84, Block No. 407, Tashan, Manama, Kingdom of Bahrain
Tel: +973 17406446
E-mail: simplex@almoayyedcg.com